

Appendix F

**HYDRAULIC ANALYSIS
RESULTS**

Scenario: 1A
Steady State Analysis
Junction Report

Label	Location Description	Elevation (ft)	Type	Base Flow (gpm)	Pressure (psi)
J-6		190.00	Demand	3.47	64.19
J-8		190.00	Demand	3.47	63.82
J-10		190.00	Demand	3.47	63.82
J-11		190.00	Demand	3.47	63.80
J-12		190.00	Demand	3.47	63.80
J-14		190.00	Demand	3.47	63.69
J-16		190.00	Demand	3.47	63.66
J-18		190.00	Demand	3.47	63.66
J-20		190.00	Demand	3.47	63.65
J-22		190.00	Demand	3.47	63.62
J-25		190.00	Demand	3.47	63.60
J-27		190.00	Demand	3.47	63.60
J-30		190.00	Demand	3.47	63.60
J-33		190.00	Demand	3.47	63.58
J-35	3rd St. & Lewis Ave. - Dist'n	190.00	Demand	3.47	63.57
J-38		190.00	Demand	3.47	63.56
J-40		190.00	Demand	3.47	63.56
J-45		190.00	Demand	3.47	63.57
J-47		190.00	Demand	3.47	63.55
J-49		190.00	Demand	3.47	63.48
J-51		190.00	Demand	3.47	63.48
J-53		190.00	Demand	3.47	63.48
J-55		190.00	Demand	3.47	63.48
J-57		190.00	Demand	3.47	63.52
J-59		190.00	Demand	3.47	63.52
J-61	3rd St. & Lewis Ave. - Transmission	190.00	Demand	3.47	63.56
J-65		190.00	Demand	3.47	63.52
J-71		190.00	Demand	3.47	63.48
J-74		190.00	Demand	3.47	63.48
J-75		190.00	Demand	3.47	63.46
J-76		190.00	Demand	3.47	63.52
J-77		190.00	Demand	3.47	63.46
J-78		190.00	Demand	3.47	63.52
J-81		190.00	Demand	0.00	63.46
J-83		190.00	Demand	3.47	63.48
J-84		190.00	Demand	3.47	63.48
J-86		190.00	Demand	3.47	63.46
J-88		190.00	Demand	3.47	63.46
J-91		190.00	Demand	3.47	63.43
J-93		190.00	Demand	3.47	63.44
J-95		190.00	Demand	3.47	63.43
J-97		190.00	Demand	3.47	63.43
J-99		190.00	Demand	3.47	63.43
J-101		190.00	Demand	3.47	63.43
J-103		190.00	Demand	3.47	63.43
J-107		190.00	Demand	3.47	63.42
J-110		190.00	Demand	3.47	63.42
J-112		190.00	Demand	3.47	63.42
J-114		190.00	Demand	3.47	63.40
J-118		190.00	Demand	3.47	63.42
J-120		190.00	Demand	3.47	63.42
J-122		190.00	Demand	3.47	63.42

Title: Gold Bar

h:\projects\01\0125000\0125101-01\dwg\gold bar.wcd Hammond Collier Wade Livingstone

10/01/02 03:58:13 PM © Haestad Methods, Inc. 37 Brookside Road Waterbury, CT 06708 USA +1-203-755-1666

Project Engineer: Eric Smith

WaterCAD v5.0 [5.0037]

Page 1 of 4